

Part 1 - General

1.01 Description

- .1 This Section specifies requirements for Contractor's use of project site.

1.02 General

- .1 The Region of Durham has arranged for easements for construction, and access as shown on Contract Drawings.

1.03 Work Areas

- .1 Do not enter upon or occupy with workers, tools or materials any lands other than public streets, roadways, right-of-ways or easements shown on Contract Drawings except after written consent has been received from property owner. Provide copies of written consent to Contract Administrator prior to entering such properties.
- .2 Supply, erect and maintain acceptable temporary fencing along working and storage areas and access routes.

1.04 Storage and Protection of Materials and Equipment

- .1 Provide suitable and adequate storage accommodation for materials and equipment during progress of work.
- .2 Comply with instructions of Contract Administrator concerning storage of equipment and materials.
- .3 Assume full responsibility for storage and protection of materials and equipment delivered to site.
- .4 Stored materials and equipment shall not block sightlines at intersections and driveways.

1.05 Access

- .1 Provide and maintain access route at all times for Emergency and Region of Durham vehicles.

- .2 Provide and maintain pedestrian and vehicular access route for landowners to cross rights-of-way, easements, or temporary work areas during all phases of construction.
- .3 Where the Contractor's operations interfere with garbage and recycling collection the Contractor shall be responsible for moving residents' garbage to a location where it can be picked up by the garbage collection crew.

END OF SECTION