

Part 1 - General

1.01 Description

- .1 This Section specifies requirements for mobilization and demobilization and shall apply only to contracts tendered by the Region of Durham.

1.02 Related Specifications

- .1 Construction Specification Section 01301 – General Instructions
- .2 Construction Specification Section 01520 – Construction Facilities

Part 2 - Products- Not Applicable

Part 3 - Execution

3.01 Mobilization and Demobilization

- .1 Move onto site and set up Contractor's office, storage facilities, equipment, sanitary facilities, electrical and communication services.
- .2 Supply, erect and maintain acceptable fencing to define Contractor's working area when working adjacent to another Contractor or in sensitive areas.
- .3 Security protection for the Contractor's office, equipment and stored materials.
- .4 Provide all necessary access to the project including haul roads as required and restoration of access routes to original condition.
- .5 Move off site all equipment and temporary facilities. Remove all surplus material and debris and restore site to original condition.
- .6 Payment - 50% of tendered lump sum for this item to be paid on first payment and 50% to be paid on Completion payment.

END OF SECTION